Category	#	Criteria	Description of Metrics
Community	C 1	Consistency with other relevant plans/improvements	Consistent with watershed, habitat, fish passage, capital improvement, and other plans that may be impacted by this project/location
	C 2	Risk of potential disturbance of cultural resources	Erosion/avulsion or flood risk or contruction risk
	C 3	Improve public access / recreational opportunity	Opportunity for community use, greenspace, etc.
	C 4	Educational opportunity	Opportunity for educational visibility
Estimated Cost	EC 1	Capital cost	Design, permitting, and construction costs
	EC 2	Long-term cost	20-year operations and maintenance costs
	EC 3	Fundability	Meets requirements of funding agencies (ECY, PSE, RCO, etc.)
Flooding & Geomorphic Hazard (Land Use and Infrastructure Risk)	FGH 1	Flooding or geomorphic hazard risk at upstream roadways	S. Superior Ave., Cedar St, S. Park Ave., Fir St. Concrete Sauk Valley Road
	FGH 2	Flooding or geomorphic hazard risk at downstream roadways	Concrete Road
	FGH 3	Flooding or geomorphic hazard risks to private properties upstream	Geomorphic hazard includes sedimentation, erosion, avulsion risks
	FGH 4	Flooding or geomorphic hazard risks to private properties downstream	to Concrete Road culvert
	FGH 5	Flooding or geomorphic hazard risks to the Skagit County shop site	
	FGH 6	Flooding or geomorphic hazard risks to the WSDOT SR20 Embankment	
Habitat and Ecological Significance	HES 1	Geomorphic resilience	Restoration of geomorphic processes that maintain and support systemwide improvements and provide resiliency to long-term changes
	HES 2	Improved fish passage through site	Potential to meet WDFW criteria, ability to benefit targeted species, channel flow status (within project area)
	HES 3	Instream physical habitat improvement	Channel habitat (complexity, bedform diversity, large wood placement, etc.) within project area
	HES 4	Floodplain connectivity and function	Ability to store water during flood events, improved floodplain connectivity and filtration (within project area)
	HES 5	Terrestrial and Riparian habitat improvement	Increased area and quality of riparian forest conditions; riparian habitat (buffer width, continuity, vegetation composition), within project area
	HES 6	Connections with existing habitat elements	Improve connections to existing wetlands, off-channel features, and riparian forest upstream/downstream of the project site (adjacent/outside of project area); reduced stranding potential
	HES 7	Degree of channel alteration	Degree of channelization and confinement, bank stabilization measures, adjacent infrastructure
Implementation and Operational Complexities	IO 1	Meets future needs for current site use	Meets County needs for snow removal equipment, storage, equipment, etc. for foreseeable future
	10 2	Permitting complexity	e.g. Hydraulic Act
	10 3	Construction complexity	Access, constructibility
	10 4	Ease of maintenance	Accessible and maintainable, comparing relative ongoing LOE/cost for maintenance
	10 5 10 6	Climate change resiliency Risk of failure	Adaptable for future changes to rainfall, temperature, creek/river levels, etc.  Risk of impacts if failure were to occur
	10 6		Complexity of other projects/work that needs to occur prior to construction of this project (e.g., acquire, design
	10 7	Sequencing complexity with other projects	and construct new maintenance facility; remove fuel tank; etc.).
Water Quality	WQ1	Reduced potential of primary WQ parameters stormwater runoff quality from Skagit County Shop site	Reduction in TSS, metals, hydrocarbons, salt, sand; improved pH, temperature
	WQ 2	Reduced potential of secondary WQ parameters stormwater runoff quality from Skagit County Shop site	Reduction in contaminants of emerging concern, etc.
	WQ3	Reduce risk of spills/illicit discharges	Reduction in potential for spills, or ability to catch spills prior to reaching creek
	WQ4	Improved long-term WQ in Lorenzan Creek	External to Skagit County Shop site
	WQ5	WQ Treatment for runoff from beyond Skagit County Shop site	e.g., SR 20 ROW, Concrete Sauk Valley Road, etc.
			•

Total count: